

CULVERTCRAWL · REQUIREMENTS

CulvertCrawl requirements

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	CVC-REQ-001	Version	0.5
Status	Draft	Date	2026-09-26
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/culvertcrawl		
Source	docs/03-requirements.md @ 2fdd39b		

REVISION HISTORY

Version	Date	Author	Change
0.5	2026-09-26	Amish Chadha	Budget approved by Amish
0.4	2026-09-25	Amish Chadha	Recommendations accepted by Amish (DDR-002)
0.3	2026-09-25	Amish Chadha	TRL 3. Record Amish's 2026-09-25 decisions (CVC-DDR-001); R12 target \$900; status from CVC-CAL-001
0.2	2026-09-25	Amish Chadha	First measurable requirements for TRL 2, with first-order status against the concept
0.1	2026-09-24	Amish Chadha	Initial scaffold

CulvertCrawl requirements

These requirements were checked by calculation at TRL 3 in CVC-CAL-001 v0.3 (docs/04-calcs/01-sizing.md). After the design changes Amish accepted on 2026-09-25 (CVC-DDR-002: 0.46 kg more ballast and the laser ring plane moved to 300 mm ahead), R2 and R5 are met on paper with thin margins, and R12 is met since Amish approved a \$910 budget on 2026-09-26 to cover the \$906 priced BOM (CVC-DDR-002). No requirement is not met. Targets are still to be validated with users (see CVC-PRB-001). The pipe range in R1 and R5 was decided by Amish on 2026-09-25 (CVC-DDR-001); the R12 budget was first set on 2026-09-25 (CVC-DDR-001) and raised to \$910 on 2026-09-26 (CVC-DDR-002). The status column is a calculated estimate, not a measurement.

The **design case** used throughout is a straight 600 mm (24 in) corrugated steel culvert, 50 m long, on a 5 % slope, with a wet silt invert and up to 150 mm of water flowing at 0.5 m/s. Unless stated, the crawler enters at the outlet and drives uphill against the flow, the worst direction. In 150 mm of water the 106 mm crawler is fully submerged. As operating guidance (CVC-DDR-002), crews should enter flooded pipes from the upstream end where access allows; the design case keeps the worst direction.

■ Requirements

ID	Requirement	Target	Verification (TRL 3 or later)	Status (CVC-CAL-001)
R1	Fit the target pipes	Drive in round pipes of 300 to 900 mm (12 to 36 in) inside diameter; crawler no wider than 180 mm and no taller than 140 mm	Model check in 300 mm and 900 mm pipe sections	Met (170 x 106 mm, 610 mm long; 50 mm or more clearance)
R2	Reach	Drive 50 m into the design case pipe and back, pulling the tether, with 20 % traction reserve	Traction and tether drag calculation; later pull test	Met on paper, thin margin (52 m wet and uphill; 56 m dry uphill; more than 90 m downhill); about 10 m if submerged track friction is 0.45
R3	Recover without entry	Crawler can be pulled out by the tether if disabled; tether break strength 1 kN or more, at least 5 times the worst stuck-pull estimate	Tether datasheet; pull calculation	Met (about 50 N locked-track pull, factor 20); jamming by debris not calculable
R4	Video	1080p video at 25 frames per second or more, live at the operator and recorded, with distance and time overlay; lighting to show the far wall of a 900 mm pipe	Camera and link budget; later image review	Met on paper (25 fps from a 50 fps stream, 53 % link use, about 370 lx); Pi 4 throughput not verifiable at TRL 3
R5	Cross-section profile	Measure the wall profile in the ring plane and report mean diameter and ovality (deflection) to within 1 % of nominal diameter, every 0.1 m of travel or less	Error budget; later calibration pipes	Met on paper: 0.24 % at 300 mm, 0.62 % at 600 mm, 0.97 % at 900 mm (thin margin); spacing 6 mm
R6	Locate observations	Distance from the pipe mouth within 1 % or 0.2 m, whichever is larger; pitch and roll within 1 degree	Encoder and IMU datasheets	Not verifiable at TRL 3 (tether slack and wheel slip)
R7	Drive in water and silt	Operate in 150 mm of water flowing at 0.5 m/s over a silt invert; survive full submersion to 1 m for 30 min (IP68 target)	Drag and buoyancy calculation; later tank test	At risk: holds in the flow on paper; IP68 not verifiable at TRL 3
R8	Climb	Hold position on a 5 % slope with power off; cross a 40 mm step or joint offset	Worm gear self-locking; track geometry	At risk: hold met; step limit between 35 and 53 mm
R9	Endurance	4 h or more of mixed driving and profiling per charge	Energy budget	Met (6.4 h nominal, 5.1 h derated)
R10	Portable and quick	Whole kit 25 kg or less, no single case over 10 kg, carried by two people in one trip; set up from vehicle to driving in 10 min or less	Mass estimate; setup sequence	Met on mass (18.1 kg; heaviest case 6.3 kg); setup time not verifiable at TRL 3
R11	Electrical and laser safety	Tether and crawler 48 V DC nominal (below the 60 V DC extra-low-voltage limit), fused, with overcurrent cutoff and an emergency stop at the surface; laser Class 2 or lower under IEC 60825-1	Design review	Met by design (10 A and 2 A fuses, 1.5 A cutoff)
R12	Affordable	Full kit (crawler, 60 m tether, reel, surface box) \$910 or less in parts, operator laptop	Priced BOM (bom/bom.csv)	

ID	Requirement	Target	Verification (TRL 3 or later)	Status (CVC-CAL-001)
		excluded (budget approved by Amish, 2026-09-26; was \$900)		Met (\$906, \$4 under). Prices are indicative, to revisit with real quotes
R13	Open and repairable	Common parts; every tether and module joint pluggable; open file formats (MP4 video, CSV profiles, JSON observation log with PACP-style codes)	Design review	Met by design

■ Requirements not met or at risk

- **R12 is met** (\$906 against \$910). It was not met by \$6 against the former \$900 budget; Amish set the budget to \$910 on 2026-09-26 to cover the priced BOM (CVC-DDR-002).
- **R2 (reach) is met on paper with a thin margin.** With the ballast plate enlarged to 2.13 kg (was 1.67 kg), the fully submerged crawler reaches 52 m driving uphill against 0.5 m/s flow (was 39 m). The result is very sensitive to track friction under water: at 0.45 it falls to about 10 m. Measuring that friction is TRL 4 work and is on hold. Entering flooded pipes from the upstream end is now operating guidance.
- **R5 at 900 mm is met on paper with a thin margin.** With the ring plane 300 mm ahead (was 200 mm), the top of a 900 mm pipe is 70.1 degrees off the camera axis (was 76.5 degrees) and the vertical diameter error is 0.97 % (was 1.59 %).
- **R7 and R8 are at risk:** seals (IP68) and the 40 mm step cannot be settled on paper.
- **R6 cannot be verified at TRL 3.**

■ Assumptions

- Track-to-silt friction coefficient about 0.6 and track motion resistance about 0.15 of weight; tether-to-pipe friction coefficient about 0.5.
- Crawler mass about 5.8 kg with ballast (3.05 kg net when submerged); tether about 55 g/m; both are estimates until parts are selected.
- 50 m reach covers most road crossings; 60 m of tether allows 10 m from the reel to the mouth.
- A 1 % profile accuracy resolves the roughly 5 % deflection limit used for plastic pipe acceptance with a 5 to 1 margin.
- The operator's own laptop runs the viewing and profiling software.