

CULVERTCRAWL · CALCULATION NOTE

CulvertCrawl sizing calculations

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	CVC-CAL-001	Version	0.5
Status	Draft	Date	2026-10-01
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/culvertcrawl		
Source	docs/04-calcs/01-sizing.md @ uncommitted		

REVISION HISTORY

Version	Date	Author	Change
0.5	2026-10-01	Amish Chadha	Budget treated as a value-engineering target
0.4	2026-09-30	Amish Chadha	Constructable design (CVC-DDR-003); masses from model volumes; fin shadow in the profiling Monte Carlo; reel and box masses from the model; 15-line BOM; R12 met to not met
0.3	2026-09-26	Amish Chadha	Budget approved by Amish (\$900 to \$910, CVC-DDR-002); script rerun; R12 not met to met
0.2	2026-09-25	Amish Chadha	Recommendations accepted by Amish (DDR-002). Ballast 230 x 80 x 14 mm; ring plane 300 mm ahead; 2,000 Monte Carlo trials; results rerun
0.1	2026-09-25	Amish Chadha	First TRL 3 sizing note (fit, mass, buoyancy, traction and reach, recovery, power, profiling error, video link, thermal, cost)

CulvertCrawl sizing calculations

Version 0.4 follows the constructable design of CVC-DDR-003, made under Amish's 2026-09-30 instruction to make the design physically buildable and open for his review. The crawler is heavier (6.63 kg, 3.77 kg net when submerged), so the wet uphill reach rises to 75 m; the boom now stands on a clear fin whose shadow is modelled in the profiling simulation, and R5 is still met (0.97 % at 900 mm). The parts added for construction raise the estimated priced BOM to \$1,034 against the \$910 value-engineering target, so R12 is over the target by \$124 (cost drivers and savings are in the design decisions register). Earlier versions follow.

Version 0.2 applies the design changes Amish accepted on 2026-09-25 (CVC-DDR-002): the ballast plate grows from 210 x 80 x 12 mm to 230 x 80 x 14 mm (1.67 to 2.13 kg), and the laser ring plane moves from 200 to 300 mm ahead of the camera. On paper the crawler now fits every target pipe, reaches 52 m in the wet uphill design case (was 39 m), profiles 300 to 900 mm pipe to within 1 % of diameter (0.97 % at 900 mm, was 1.59 %), runs 6.4 h per charge and stays within safe extra-low voltage. R2 and R5 are met with thin margins. Version 0.3 records the budget Amish approved on 2026-09-26: `budget_usd` is \$910, which covers the \$906 priced BOM, so R12 is now met and no requirement is not met. R7 (IP68) and R8 (40 mm step) are at risk, and R6 (distance) cannot be verified until hardware exists, which is TRL 4 work and on hold by Amish's instruction.

Every number in this note is printed by `docs/04-calcs/sizing.py` (run from the repo root: `python docs/04-calcs/sizing.py`), which also writes `docs/04-calcs/results.csv`. The script reads its dimensions from `cad/src/model.py` (`PARAMS`) and the cost from `bom/bom.csv`, so the note, the model and the BOM share one source. All values are first-principles estimates; nothing here is measured.

■ 1. Assumptions

Table 1. Inputs. All are assumptions for a paper design.

Input	Value	Basis
Design case	Straight 600 mm corrugated steel culvert, 50 m, 5 % grade, wet silt invert, 150 mm of water at 0.5 m/s	CVC-REQ-001
Track to silt friction	0.6, dry or submerged (sensitivity at 0.45)	Typical rubber on wet fine soil
Track motion resistance	0.15 of normal load	Soft silt
Tether to invert friction	0.5	PU jacket on wet steel or silt
Traction reserve	20 %	R2
Tether	7 mm OD, 55 g/m in air, 2 x 0.75 mm ² class 5 copper at 26 Ω/km (IEC 60228 maximum at 20 °C)	Estimate until a cable is chosen
Crawler loads	Drive 12 W, LEDs 8 W, Pi, camera and network 6.5 W, laser, IMU and sensors 1.5 W; 50 W peak	TRL 2 load list, kept
Converters	Buck 91 %, boost 92 %; surface electronics 1 W	Datasheet class
Battery	12.8 V 20 Ah LiFePO ₄ , 90 % depth of discharge, 20 % derating for cold and ageing	Decided (CVC-DDR-001)
Crawler drag	Cd 1.1 on 170 x 106 mm frontal area	Bluff box
Camera	IMX708 at 2304 x 1296, 50 frames per second, LEDs and laser on alternate frames	Chosen here to meet R4 and R5 together
Lens	180 degree equidistant circular fisheye, image circle 1296 px, so 0.139 degree per pixel	See section 6
Profiling errors (1 sigma)	Ring center 0.3 px random; lens model residual 0.3 px at the image edge; ring plane tilt 0.1 degree; ring plane distance 0.3 mm; crawler yaw uniform within 2 degrees	Calibration in a reference pipe assumed
Ring plane	300 mm ahead of the dome center (200 mm in v0.1)	Decided (CVC-DDR-002)
Ballast	Steel plate 255 x 88 x 14 mm, 8 mm above the track contact line (230 x 80 x 14 mm in v0.3; 210 x 80 x 12 mm in v0.1)	CVC-DDR-002; resized for construction, CVC-DDR-003
Made parts	Masses from the model volumes in <code>cad/src/model.py</code> : 6061 at 2.70 kg/L, steel 7.85, acrylic 1.19, PETG 1.07, HDPE 0.95, PVC 1.40, plywood 0.60	CVC-DDR-003
Boom fin	8 mm clear acrylic in the vertical plane through the camera axis, from 131 to 262 mm ahead of the hull centre; points whose ray from the lens passes through it are dropped	CVC-DDR-003

■ 2. Geometry and fit (R1)

The model (`cad/src/model.py`, drawing CVC-DWG-001 Rev P3) gives a crawler 170 mm wide over the tracks, 106 mm high over the bezel and 611 mm long from the rear strain relief to the laser end cap (track length 270 mm). The belts are now 36 mm wide with the same outer edge, so the contact geometry below is unchanged. The fit check

below is for straight pipe; the boom overhangs the tracks by about 300 mm, so tight bends and offset joints need the removable boom question settled (still open). The outer track edges bear on the curved invert. Table 2 shows that the crawler clears the wall by at least 50 mm in every target pipe.

Table 2. Fit in the target pipes.

Pipe	Track contact line above invert	Camera axis above invert	Least clearance to wall	Normal load factor
300 mm	26.4 mm	88.4 mm	50 mm	1.214
600 mm	12.3 mm	74.3 mm	66 mm	1.043
900 mm	8.1 mm	70.1 mm	69 mm	1.018

The track edges meet the 600 mm wall at 16.5 degrees, so the sum of the normal forces is 1.043 times the weight. This raises both traction and track resistance in proportion. The TRL 2 figure of 125 mm height is replaced by 106 mm.

■ 3. Mass and buoyancy (R7, R10)

Table 3. Crawler mass.

Item	Mass	Basis
Hull body and lid	1.26 kg	Model volume, 6061 (1.09 kg in v0.3, before the rim, pads and 10 mm front wall)
Track belts, sprockets, idlers	1.00 kg	Hobby track sets
Side plates	0.19 kg	Model volume, 6061
Worm gear motors	0.70 kg	2 x 0.35 kg, 5840 class
Electronics stack	0.20 kg	
Electronics tray and camera mount	0.05 kg	Model volume
Camera, dome, LEDs	0.15 kg	
Front bezel	0.06 kg	Model volume, 6061
Laser projector: fin, bracket, boom, head	0.13 kg	Model volume plus 0.02 kg for the diode and mirror (0.11 kg in v0.3)
Ballast plate	2.45 kg	Model volume, steel (2.13 kg in v0.3)
Fasteners, eye bolt, seals, penetrator, strain relief	0.45 kg	Allowance (0.40 kg in v0.3)
Crawler	6.63 kg	5.77 kg in v0.3; 5.31 kg in v0.1

Fully submerged, the crawler displaces 2.87 L, so its net mass is 3.77 kg (3.05 kg in v0.3): 57 % of the dry normal load is left for traction. In the design case the water is 138 mm deep above the track contact line, deeper than the 106 mm crawler, so the crawler **is fully submerged**. The TRL 2 reach estimate did not account for this.

The whole kit weighs 22.2 kg (crawler 6.6 kg, tether 3.3 kg, reel, frame and counter 4.5 kg, surface box 7.6 kg, gamepad 0.2 kg; was 18.1 kg). The reel and box figures now take their made parts from the model. The heaviest single item is the reel with its tether, 7.8 kg. R10 is still met.

■ 4. Traction and reach (R2, R8)

Reach is the tether length whose drag uses up the traction left after track resistance, grade and water drag. When the crawler drives uphill it must also lift the tether up the grade, so the drag per meter is the tether weight times $(0.5 \cos \alpha + \sin \alpha)$. The TRL 2 estimate used $0.5 \times$ weight only and did not model water. Table 4 gives the result in each direction.

Table 4. Reach in a straight 600 mm pipe on a 5 % grade, with 20 % traction reserve.

Case	Usable traction	Track resistance	Grade	Water drag	Tether drag	Reach
Dry, uphill (enter at the outlet)	32.5 N	10.2 N	3.25 N	0	0.296 N/m	64 m
Dry, downhill (enter at the inlet)	32.5 N	10.2 N	-3.25 N	0	0.242 N/m	106 m
Design case wet, uphill against 0.5 m/s flow	18.5 N	5.8 N	1.84 N	4.19 N	0.089 N/m	75 m
Design case wet, downhill with the flow	18.5 N	5.8 N	-1.84 N	-1.21 N	0.073 N/m	216 m

- **R2 is met on paper.** Submerged and driving upstream, the crawler reaches 75 m against a 50 m target (52 m in v0.3, 39 m in v0.1); the gain comes from the 0.86 kg the constructable design added. With no reserve, the dry uphill reach is 92 m.
- **The wet result is still very sensitive to track friction under water.** At a friction coefficient of 0.45 instead of 0.6, wet uphill reach falls to about 23 m (about 10 m in v0.3). This is the least certain input in the note, and measuring it is TRL 4 work, on hold by Amish's instruction.
- Entering from the upstream end (downhill, with the flow) gives more than 100 m in both cases, and is operating guidance for flooded pipes (CVC-DDR-002). On the way back the reel winds the tether in, and the crawler still has a 6.7 N margin reversing upstream.
- The plate now sits 8 mm above the track contact line (10 mm in v0.1), so ground clearance under the skid is 2 mm less.
- Sprocket torque at the dry traction limit is 0.84 N·m per motor (0.73 N·m in v0.3), including 85 % belt efficiency, within a 1 N·m worm gear motor. Top speed at 80 rpm is 0.29 m/s.

R8. On a 5 % grade the crawler needs 3.25 N to hold against 40.7 N of static friction, and the self-locking worm gears hold it with power off. The water drag on a stationary, submerged crawler in 0.5 m/s flow is 2.5 N against 23.1 N of static friction. For the 40 mm step, a conservative rule for a flat track limits the step to the idler radius, 35 mm; a friction bound, $r(1 + \sin(\tan \mu))$, gives 53 mm at $\mu = 0.6$ and 48 mm at $\mu = 0.4$. **R8 step crossing is at risk.**

■ 5. Recovery pull (R3)

With both tracks locked (worm gears self-locking) and 50 m of tether uphill of the crew, the pull to drag the crawler out is about 59 N. The 1 kN aramid member, now tied to an eye bolt in the ballast plate (CVC-DDR-003), gives a factor of 17 on that pull; at the required factor of 5 it covers a stuck pull of 200 N. A crawler jammed by debris cannot be bounded by calculation. The crew should never use a vehicle to pull the tether.

■ 6. Power, tether and endurance (R9, R11)

Table 5. Power while driving and profiling.

Quantity	Value
Crawler loads	28.0 W
Crawler input (after 91 % buck)	30.8 W
Tether loop resistance, 2 x 60 m	3.12 Ω
Tether current at 48 V	0.67 A
Voltage at the crawler	45.9 V
Tether copper loss	1.40 W (4.4 %)
Boost output	32.2 W
Battery output, including 1 W of surface electronics	36.0 W
Peak: tether current, crawler voltage, drop	1.25 A, 44.1 V, 3.9 V
Peak battery current at 12.0 V	5.4 A
Tether loss if the tether ran at 24 V	8.24 W
Usable battery energy (256 Wh nominal)	230 Wh
Endurance	6.4 h nominal; 5.1 h derated

R9 (4 h) is met. At 24 V the tether would lose 8.24 W, about six times more, which supports the 48 V decision. The peak battery current of 5.4 A would blow the 5 A fuse listed at TRL 2, so the BOM now has a 10 A fuse at the battery and a 2 A fuse on the 48 V output, with the overcurrent cutoff at 1.5 A (R11).

■ 7. Laser ring profiling (R5)

The lens must see the ring at up to 70.1 degrees off axis. With the camera 70 mm above the invert of a 900 mm pipe and the ring plane 300 mm ahead, the top of the pipe is 70.1 degrees off the camera axis (60.3 degrees in 600 mm, 35.2 degrees in 300 mm). At the v0.1 distance of 200 mm it was 76.5 degrees in 900 mm pipe, where the fisheye is least accurate. A 160 degree lens on a 16:9 frame, as assumed at TRL 2, cannot see that far vertically. The design therefore uses a 180 degree circular fisheye whose image circle fits the 1296 px sensor height, at 0.139 degree per pixel (TRL 2 assumed 0.1 degree per pixel).

The script simulates 2,000 ring measurements per case (400 in v0.1; the larger sample cuts the scatter of the 95th percentile from about 0.1 to about 0.03 percentage points): it projects the wall points in the true (tilted, offset, yawed) light plane, adds lens and centroid errors, triangulates on the nominal plane as the software would, fits an ellipse and compares the result with the true pipe.

The boom now stands on a clear 8 mm fin in the vertical plane through the camera axis (CVC-DDR-003). The camera sees it edge on, and it hides the wall points whose rays pass through it: 6.4 % of the ring in 300 mm pipe and 2.1 % in 900 mm pipe, all at the invert. Version 0.4 drops those points before the fit.

Table 6. Profiling error, ring plane 300 mm ahead, fin shadow included, 95th percentile of 2,000 trials.

Pipe	Water depth	Mean diameter error	Vertical diameter error	Worst wall point	R5 (1 %)
300 mm	0	0.24 %	0.25 %	1.4 mm	Met
600 mm	0	0.43 %	0.55 %	4.1 mm	Met
600 mm	150 mm	0.44 %	0.57 %	4.1 mm	Met
900 mm	0	0.71 %	0.93 %	9.0 mm	Met, thin margin
900 mm	150 mm	0.74 %	0.97 %	9.4 mm	Met, thin margin

Without the fin the 900 mm case gives 0.95 %; the difference is within the scatter of the simulation, so the fin does not change the R5 result.

For comparison, the same simulation with the v0.1 ring plane at 200 mm gives 1.41 % in 900 mm pipe (1.49 % in v0.3, without the fin) with 150 mm of water (reported as 1.59 % from 400 trials in v0.1). The 300 mm plane was decided by Amish on 2026-09-25 (CVC-DDR-002) and costs a 100 mm longer boom. A 5 % deflection limit is 30 mm in a 600 mm pipe, so even a 1.5 % error would still flag a failed pipe; R5 asks for a tighter, acceptance-grade number.

With the camera at 50 frames per second and the laser on alternate frames, the crawler takes 25 profiles per second: one every 6 mm at 0.15 m/s and every 12 mm at top speed (R5 asks for 0.1 m or less).

Signal. A 1 mW ring spread around a 900 mm pipe puts 0.177 W/m^2 on the wall inside a 2 mm line. On a wall of 20 % reflectance, at f/2 and 10 ms, a $2.8 \mu\text{m}$ binned pixel collects about 272 signal electrons, a shot-noise limited SNR of about 16, enough in a dark pipe with the LEDs dimmed. Sunlight at the mouth is not modeled. A 7 mm pupil 100 mm from the cone receives about $11 \mu\text{W}$, well under the 1 mW Class 2 limit.

■ 8. Video, data link and lighting (R4, R6)

- **Video.** The LED frames of the 50 fps stream give 25 fps video, meeting R4, encoded as 1080p H.264 at about 8 Mbit/s. Laser frames go to the laptop as 1296 x 1296 grey JPEG at about 42 Mbit/s (1 bit per pixel assumed). Together they use about 53 % of the roughly 94 Mbit/s usable on 100BASE-TX. Whether a Pi 4 can capture at 50 fps and run both encoders at once cannot be verified at TRL 3.
- **Lighting.** 800 lm in a 120 degree cone gives about 255 cd: about 370 lx on the far wall of a 900 mm pipe and about 64 lx 2 m ahead down the pipe.
- **Distance (R6).** A 50 mm payout wheel with a 600-count encoder resolves 0.26 mm. The R6 tolerance at 50 m is 0.5 m. Tether slack, snaking and wheel slip set the real error and cannot be verified at TRL 3.

■ 9. Hull thermal and pressure

About 11.0 W is dissipated inside the hull, which has 0.095 m^2 of outer area. In air ($h = 8 \text{ W/(m}^2 \text{ K)}$) the hull runs about 15 K above ambient, so about 55 °C at a 40 °C ambient; the Pi needs a heat path to the hull wall. In water the rise is 0.4 K. The IP68 target of 1 m is only 9.8 kPa, so hull stress is negligible; the seals, not the walls, set R7.

■ 10. Cost (R12)

Version 0.4. The BOM has 15 lines, every one priced. The total is **\$1,034** against the value-engineering target of \$910 (`budget_usd` , a hypothetical control target, not a limit), **\$124 over** (crawler, lines 1 to 8, 14 and 15, \$481; tether, reel and surface kit \$513; hardware and consumables \$40). The parts added to make the design buildable (CVC-DDR-003) account for all of the increase: the front bezel and the side plates and small made parts (new lines 14 and 15, \$32), the reel frame, bearings, hubs and counter reader (\$43), the surface box chassis (\$20), the hull rim and pads (\$8), the laser fin, window and cap (\$8), the larger ballast plate (\$4), the deck (\$3) and the eye bolt and screws (\$10). **R12 is over the value-engineering target by \$124.** `budget_usd` is not changed; cost drivers and savings worth trying are in the Value engineering section of the design decisions register.

Version 0.3. The BOM had 13 lines and totalled **\$906** against the value-engineering target of \$910, a margin of **\$4** (crawler \$426, tether, reel and surface kit \$450, hardware and consumables \$30). The larger ballast plate adds \$3 and the longer laser boom \$2. Against the former \$900 budget the margin was -\$6; Amish accepted the v0.1 overrun of \$1 as within pricing uncertainty (CVC-DDR-002) and on 2026-09-26 set the target to \$910 to match the priced BOM. R12 was within the target in v0.3.

■ 11. Results against requirements

Table 7. Every requirement in CVC-REQ-001 v0.7, with its calculated value and status.

ID	Requirement	Target	Calculated value	Status
R1	Fit	300 to 900 mm pipe; 180 mm wide, 140 mm high or less	170 x 106 mm, 611 mm long; 50 mm or more clearance	Met
R2	Reach	50 m in the design case with 20 % reserve	75 m wet uphill; 64 m dry uphill; 106 to 216 m downhill; about 23 m at friction 0.45	Met on paper (sensitive to friction)
R3	Recover without entry	1 kN, 5 times the worst stuck pull	59 N locked-track pull; factor 17	Met (jamming not calculable)
R4	Video	1080p, 25 fps or more; far wall of 900 mm pipe lit	25 fps; 53 % link use; 370 lx	Met on paper (Pi 4 throughput not verifiable at TRL 3)
R5	Profile	1 % of diameter; every 0.1 m or less	0.25 % (300 mm), 0.57 % (600 mm), 0.97 % (900 mm), fin shadow included; 6 mm spacing	Met on paper (thin margin at 900 mm)
R6	Locate	1 % or 0.2 m; pitch and roll 1 degree	0.26 mm encoder resolution; slack and slip unknown	Not verifiable at TRL 3
R7	Water and silt	150 mm at 0.5 m/s; IP68 to 1 m	Holds with 2.5 N drag against 23.1 N; fully submerged in the design case	At risk (IP68 not verifiable at TRL 3)
R8	Climb	Hold on 5 % unpowered; 40 mm step	Hold: 3.25 N against 40.7 N; step 35 to 53 mm	At risk (step)
R9	Endurance	4 h or more	6.4 h nominal; 5.1 h derated	Met
R10	Portable	25 kg kit, 10 kg per case; setup 10 min	22.2 kg; heaviest item 7.8 kg (reel with tether)	Met on mass; setup time not verifiable at TRL 3
R11	Electrical and laser safety	48 V DC, fused, cutoff, stop; Class 2	48 V, 2 A and 10 A fuses, 1.5 A cutoff; 11 μ W at the pupil	Met by design
R12	Affordable	\$910 or less	\$1,034	Over the value-engineering target by \$124 (parts added for construction)
R13	Open and repairable	Common parts, pluggable joints, open formats	Design review	Met by design

Summary: 1 over its value-engineering target (R12), 2 at risk (R7, R8), 1 not verifiable at TRL 3 (R6), 9 met on paper (R1, R2, R3, R4, R5, R9, R10, R11, R13), of which R5 has a thin margin at 900 mm and R2 is sensitive to submerged track friction. In v0.3 R12 was met at \$906; in v0.2, R12 was over the former \$900 target; in v0.1, R2 and R5 were not met.